



- NOTES:**
1. STUB OUT MUST BE HYDROSTATICALLY TESTED WITH REST OF WATER MAIN
  2. IN LIEU OF SLIP-JOINT AND COMPRESSION PLUG, AN M.J. JOINT MAY BE USED WITH AN M.J. PLUG
  3. REFER TO DWG. NO. 127 FOR RODDING RESTRAINTS

FULTON COUNTY STANDARD DETAIL 124  
 STUB OUT DETAIL

DATE	REVISIONS	DATE	REVISIONS	DCS/DRN/CHKD: CMS	APPROVED: REW	DATE: 12-2-05
B/08	NRR					



FULTON COUNTY PUBLIC WORKS  
 141 PRYOR ST. ATLANTA, GA. 30303  
 404-612-7400 FAX: 404-224-0498

DRAWING NO. 124