



FULTON COUNTY PURCHASING DEPARTMENT
Winner 2000 – 2004 Achievement of Excellence in Procurement Award
National Association of Purchasing Management

Jerome Noble, Director
July 18, 2005

Addendum Number 2 – Invitation to Bid # 05ITB45495C
Heavy Equipment

Dear Vendors:

This addendum is in reference to **Invitation to Bid # 05ITB45495C – Heavy Equipment** in support of the Fulton County Public Works Department. This addendum provides additional information, requirements, terms and clarifications about this project. The following questions were submitted and are responded to:

Submitted by: **Tim Conger**
Adams Equipment Company, Inc.
(404) 307-6927

QUESTIONS: Mower. The scope says that specifications cover one Tractor w/96" Rear PTO Driven Flail Mower. Is this bid for a Tractor w/96" Rear PTO Driven Flail Mower only, I do not see any specifications for the 90" Side Mounted Flail Mower. Tractor with/96" Rear PTO Driven Flail Mower with a 90" Side Mounted Flail attachment.

RESPONSE: Yes, we are requesting a Tractor with/96" Rear PTO Driven Flail Mower with a 90" Side Mounted Flail attachment.

The specs for the side mower is as followed:

1. Cutting width on TSF-90c is 90" of actual cut.

Bidders Response: _____

2. Side cutter assembly shall be flail-type, hydraulically powered.

Bidders Response: _____

3. Cutter shafts shall be dynamically balanced, 6" diameter, 3/8" wall tubing with 2 3/16" diameter stub shafts and bearings.

Bidders Response: _____

4. Cutter head shall have a 96 forged, self cleaning, reversible all purpose knives, or 48 smooth cut knives.

Bidders Response: _____

5. Knife interchangeability shall not require change of cutter shaft.

Bidders Response: _____

6. Cutting height shall be infinitely adjustable between $- \frac{1}{2}$ " to +6".

Bidders Response: _____

7. Cutter shafts will have bearing wrap protection.

Bidders Response: _____

8. All cutter heads shall have 6-5/8" diameter rollers, 1-3/8" double-row spherical bearings and replaceable 1-3/8" stub shafts with external bearing hub caps and cap retainers.

Bidders Response: _____

9. Cutter head are shall be 159 degree from vertical position.

Bidder's Response: _____

10. Cutter heads shall have 10 gauges, 80,000 lb yield steel bonnet; $\frac{1}{2}$ " drive side and 3/8" carrier steel end plates.

Bidders Response: _____

11. Cutter head shall have replaceable skid shoes.

Bidders Response: _____

12. Cutter head shall have 20-1/4" of inboard travel.

Bidders Response: _____

13. Cutter shall be rated at maximum 2,400 RPM.

Bidders Response: _____


14. Knife swing circumference shall be a minimum of 58 1/2".

Bidders Response: _____

The undersigned proposer acknowledges receipt of this addendum by returning (1) copy with the proposal by the bid due date and time. Failure to include a signed copy of this addendum with your proposal documents could render your proposal non-responsive.

Except as provided herein, all terms and conditions in the ITB referenced above remain unchanged and in full force and effect.

Sincerely,



William E. Long, Jr.
Chief Assistant Purchasing Agent

ACKNOWLEDGMENT OF RECEIPT OF ADDENDUM NUMBER 1