



Fulton County, GA

Department of Purchasing & Contract Compliance

Felicia Strong-Whitaker, Interim Director

April 4, 2013

Re: #13ITB87339K-LW, Juvenile Court Building Entrance Security Renovation

Dear Bidders:

Attached is one (1) copy of Addendum #2, hereby made a part of the above referenced Invitation to Bid (ITB).

Except as provided herein, all terms and conditions in the ITB referenced above remain unchanged, in full force and effect.

Sincerely,

Linda Walton

Linda Walton
Assistant Purchasing Agent

Winner 2000 - 2009 Achievement of Excellence in
Procurement Award • National Purchasing Institute



This Addendum forms a part of the contract documents and **modifies** the original ITB documents as noted below:

- Attachment of the revised Table of Contents
- Attachment of the Juvenile Court Logo
- Attachments of the revised Drawings A-1.2 and E-1.1 (available for pick up or email from Action Blueprint)

RESPONSE TO QUESTIONS AND INQUIRIES:

Q1: I recently read the specifications for the above project and noticed that Kevlar ballistic panels were identified. Our company, Waco Composites, manufactures ArmorCore® Bullet Resistant Fiberglass Panels. This material offers the same ballistic qualities as Kevlar but for a quarter of the cost. Would there be any chance you would consider this product as well?

A1: The ArmorCore® material may be substituted for the Kevlar ballistic panels listed in the specifications. This material should be easier to install and it can take a number of bullet hits without having to be replaced.

Q2: What is the make and model of the existing CCTV system?

A2: DCRM: Pelco DX 8100-DX 8132-1500

Q3: What is the make and model of the existing lobby cameras?

A3: Pelco ICS310-CRV39A 24vac/12vdc

Q4: How many unused camera ports are available on the existing CCTV system?

A4: 7 Free ports

Q5: Will additional licensing be required in order to accommodate the additional cameras?

A5: No. This is not in the scope of work and will be done under a separate contract.

Q6: Will ceiling-mounted cameras be acceptable in the areas with drop ceilings?

A6: Yes

Q7: Will a camera be required in the pat down room?

A7: Yes. A camera will be required for Room 108.

Q8: What is the make and model existing access control system?

A8: Manufacture: Infographics Systems Model: ACU2

Q9: What type of access cards are currently in use?

A9: HID proxCard II

Q10: Will any of the exterior turnstile doors or conventional doors require card readers?

A10: No

Q11: Will one the interior turnstiles be used as employee access point requiring a card reader?

A11: No. Turnstiles are used to restrict entry into building only.

Q12: Will the remote locking mechanism operate locks on all doors simultaiously?

A12: Yes. It is the intent for authorized staff to have the ability to lock down the lobby entrances during an emergency.

Q13: Are there there any access control devices or remote locking systems on the existing doors?

A13: No

Q14: On drawing A-1,2 indicates the camera closest to the reception desk should be replaced with a camera that has a pan mechanism. Note 6 on the same page mentions Five cameras w/zoom mechanism. Does this camera require tilt and zoom functions also?

A14: This scope of work will be under a separate contract.

Q15: Does the metel detector need to have the capability of adding management software at a later date or do you require the management software to be installed at the time of metal detector installation?

A15: The management software is required to be installed at the time of the metal detector installation.

Q16: What are the liquidated damages for the subject project?

A16: There are no liquidated damages for this project.

Q17: Will the following products also be required? Complete Metor 28 Hand-Held Metal Detector; Metor HG 32/100 handgun frame replica; Metor CK 10 pocket Knife; Metor SSK 12 Pocket Knife?

A17: No. This is not in the scope of work

Q18: Contract Specification: 00020 Invitation to Bid Page 13 items "F,G, & H". Form "F" Declaration of Employee-Number Categories is missing but Labeled as Form F "Georgia Security and Immigration Contractor Affidavit and Agreement. Form H "Georgia Security and Immigration Subcontractor Affidavit" is Labeled as Form "G". Please correct Forms; listing and provide missing Form Declaration of Employee-Number Categories".

A18: See Addendum #1 for the correction

Q19: Specification 001000.U – Does the affidavit go on the outside of the envelope or is the first page on top of the bid/proposal? Please clarify location of this document.

A19: The Georgia Security and Immigration Contractor/Subcontractor Affidavits do not have to be placed on the outside of the envelope or as the first page of the bid. These are Purchasing Forms "F" and "G" and can be submitted with the bid in sequence with the other Purchasing Forms. (A-G)

Q20: Table of contents has division 4 to labeled incorrectly. Example Division 4 is not wood and plastics and if so then all of the sub specifications should start with a 4 not a 6, please correct.

A20: See the attachment for the revised Table of Contents.

Q21: A-1.3 provide specification and detail for replacement of expansion joint.

A21: The contractor must match existing expansion joint cover /cross section configuration with a new stainless steel cover. It is the intent for the new expansion joint cover to be compatible with the existing floor conditions.

Q22: Your agenda notification has deadline for questions as Monday APRIL 2nd Tuesday is the 2nd. Clarify.

A22: The deadline to submit questions and inquiries for this project is Tuesday, April 2, 2013.

Q23: Provide specification for camera.

#13ITB87339K-LW, Juvenile Court Building Entrance Security Renovation
Addendum #2
Page Five

- A23: Cameras will be under a separate contract. All identified new camera locations will require the contractor to provide data pulls ONLY. Power is not required unless there are Ptz (Pan tilt zoom) cameras. The actual data will be pulled by in house contractors. Note: Raceway is required where necessary, which is typically where drop ceilings are not in the path of the complete cable run. A pull string in any raceway is required
- Q24:** Provide detail and drawings on how temporary security walls are to be constructed when demolition of the storefront system.
- A24: Means and methods are the contractor's responsibility. Fulton County's expectations for the temporary wall are as the following: 1. Minimize dust and debris exposure in non-construction areas ; 2. Protection and safety of staff and visitors; 3. Design within code and fire safety guidelines; 4. Do not block daily activity of staff/ visitors and egress.
- Q25:** How high up on the two tall walls are we to repaint. Provide color numbers for touch up.
- A25:** Painting is required for damaged and renovated wall surfaces. The contractor must feather new paint into existing painted wall. The paint color to be matched by utilizing a sample removed from the existing demolished drywall.
- Q26:** Working at night, will the center have a full time security person on staff all night? If so, who is responsible for this cost? If contractor, provide hourly cost rate.?
- A26: Yes. The Sheriff's Department will be responsible for security. Security will not be in the contractor's scope of work.
- Q27:** Who is responsible for the cost of the permit?
- A27: The contractor will be responsible for obtaining and purchasing the permit.
- Q28:** There were two sign in sheets, one for the meeting and one for the site visit. You only posted one, please post the other and label which one is which.
- A28: The Pre-Bid Sign-In Sheet is the required document that must be posted on the County's website. The names on the Pre-Bid Sign-In Sheet and the Mandatory Site Visit Sign-In Sheet were the same.
- Q29:** Drawing 1/A-2.3 provide missing details 2/A2.3 and 3/A2.3 as referenced.
- A29: As indicated on the drawings, the metal bench has been removed. The contractor is to provide an allowance of \$2,200 for seating.

#13ITB87339K-LW, Juvenile Court Building Entrance Security Renovation
Addendum #2
Page Six

Q30: On the two wing walls Left & Right) of the reception desk, is there any Level III Kevlar Panels?
Drawings do not indicate any.

A30: Yes. Kevlar Level 3 walls are indicated on the plans.

Q31: B/A2.3 show 6 lockers with doors and 6 cubby holes. Are there 12 lockers?

A31: Yes there are 12 lockers.

Q32: Provide specifications for CMU, none listed.

A32: The contractor should match existing CMU.

Q33: A1.5 Shows a County Seal in the middle of the room with no dimension or a detail with verbiage or speciation further defining the seal. Who is to provide this?

A33: See attachment logo for verbiage. The contractor is to provide seal. Seal dimension to be determined in field (we project the seal size to be 6ft to 8ft in diameter). The contractor is to provide a mock up sample to determine an appropriate logo size

Q34: Specification 09620 only indicates water cut County seal, provides additional information.

A34: The contractor should refer to a license marmoleum manufacture for details for the water cut artwork process.

#13ITB87339K-LW, Juvenile Court Building Entrance Security Renovation
Addendum #2
Page Seven

ACKNOWLEDGMENT OF ADDENDUM #2

The undersigned proposer acknowledges receipt of this addendum by returning one (1) copy of this form with the bid package to the Purchasing Department, Fulton County Public Safety Building, 130 Peachtree Street, Suite 1168, Atlanta, Georgia 30303 by the bid due date and time **Thursday, April 11, 2013, 11:00 A.M.**

This is to acknowledge receipt of Addendum #2, _____ day of _____, 2013.

_____ Legal Name of Proposer

_____ Signature of Authorized Representative

_____ Title

Table of Contents

Juvenile Court Security Entrance Renovations

395 Pryor Street, NW -- Atlanta, GA 30312

Section

Title

Division 0 – Bidding and Contract Requirements

00020 INVITATION TO BID

- Description of Project
- Permits
- Rights of Way/Easements
- Bid Documents
- Subcontracting Opportunities
- Term of Contract
- No Contact Provision
- Bid Contact
- Basis of Award
- Pre-Bid Conference

00100 INSTRUCTIONS TO BIDDERS

- A. Contract Documents
- B. Bid Preparation and Execution
- C. Addenda and Interpretations
- D. Site Examination
- E. Bidder's Modification and Withdrawal of Bids
- F. Bid and Contract Security
- G. Right to Reject Bids
- H. Applicable Laws
- I. Examination of Contract Documents
- J. Indemnification and Hold Harmless Agreement
- K. Bid Opening
- L. Determination of Successful Bidder
- M. Georgia Utility Contractors License
- N. General Contractors License
- O. Professional Licenses
- P. Wage Clause
- Q. Notice of Award of Contract
- R. Execution of Contract Documents
- S. Joint Venture
- T. Contractors Compliance with Procurement
- U. Georgia Security and Immigration Compliance Act
- V. Bid General Requirements

Required Bid Submittal Checklist for ITB

00410 BID BOND

00420 PURCHASING FORMS & INSTRUCTIONS

- Form A - Non-Collusion Affidavit of Prime Bidder/Offeror
- Form B - Certificate of Acceptance of Request for Bid Requirements
- Form C - Professional License Certifications
 - Form C1 – Georgia Utility License Contractors License
 - Form C2 – Georgia General Contractors License

Form C3 – Georgia Professional License
 Form D - Certification Regarding Debarment
 Form E - Disclosure Form & Questionnaire
 Form F – Georgia Security and Immigration Contractor Affidavit and Agreement
 Form G – Georgia Security and Immigration Subcontractor Affidavit

00430 CONTRACT COMPLIANCE REQUIREMENTS

Non-Discrimination in Contracting and Procurement
 Required Forms and EBO Plan
 Exhibit A – Promise of Non-Discrimination
 Exhibit B – Employment Report
 Exhibit C – Schedule of Intended Subcontractor Utilization
 Exhibit D – Letter of Intent to Perform As a Subcontractor or Provide
 Materials or Services
 Exhibit E – Declaration Regarding Subcontracting Practices
 Exhibit F – Joint Venture Disclosure Affidavit
 Exhibit G – Prime Contractor/Subcontractor Utilization Report
 Exhibit H - First Source Jobs Program Agreement
 Equal Business Opportunity Plan (EBO Plan)

00490 INSURANCE AND RISK MANAGEMENT PROVISIONS

00500 CONTRACTUAL AGREEMENT

00610 PERFORMANCE BOND REQUIREMENTS

00620 PAYMENT BOND REQUIREMENTS

00700 GENERAL CONDITIONS

00800 SPECIAL CONDITIONS

Division 1 – General Requirements

01010 SUMMARY OF WORK

01200 PROJECT MEETINGS

01320 SCHEDULE OF VALUES

01320A REFERENCES

01320B CUTTING AND PATCHING

01320C ABBREVIATIONS

01326 CONSTRUCTION SCHEDULES

01330 SUBMITTALS

01520 TEMPORARY FACILITIES

01710 SELECTIVE DEMOLITION

01720 F.C. DESIGN STANDARDS

01720A GENERAL REQUIREMENTS

Division 2 – Sitework

02111 BUILDING DEMOLITION

Specifications Table of Contents

02630 PORTLAND CEMENT CONCRETE SIDEWALKS

Division 3 – Concrete

03300 CAST-IN-PLACE CONCRETE

Division 4 – Masonry (NIC)**Division 5 – Metals (NIC)****Division 6 – Wood and Plastic**

06100 ROUGH CARPENTRY

06200 FINISH CARPENTRY

Division 7 – Thermal and Moisture Protection

07840 FIRESTOPPING

07900 CAULKING AND SEALANTS

Division 8 – Doors and Windows

08110 STEEL DOORS & FRAMES

08219 FLUSH WOOD DOORS

08311 ACCESS DOORS

08410 STOREFRONT FRAME

08470 REVOLVING ENTRANCE DOORS

08510 STEEL WINDOWS

08520 ALUMINUM WINDOWS

08710 DOOR HARDWARE

Division 9 – Finishes

09250 GYPSUM BOARD

09511 ACOUSTICAL PANEL CEILINGS

09620 RESILIENT LINOLEUM FLOORING

09680 CARPET

09912 INTERIOR PAINTING

Division 10 – Specialties

10431 SIGNAGE

10454 TURNSTILES / GATES

10505 METAL LOCKERS

10510 PISTOL LOCKERS

Division 11 – Equipment

11910 METAL DETECTORS

Specifications Table of Contents**Division 12 – Furnishings (NIC)****Division 13 – Special Construction (NIC)****Division 14 – Conveying Systems (NIC)****Division 15 – Mechanical**


15000	MECHANICAL GENERAL REQUIREMENTS
15762	CABINET UNIT HEATERS
15820	DUCT ACCESSORIES
15855	DIFFUSERS, REGISTERS, AND GRILLES
15990	TESTING, ADJUSTING, & BALANCING


Division 16 – Electrical

16060	GROUNDING AND BONDING
16073	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
16075	ELECTRICAL IDENTIFICATION
16091	SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING
16092	SLEEVES AND SLEEVE SEALS FOR COMMUNICATIONS PATHWAYS AND CABLING
16120	CONDUCTORS AND CABLES
16130	RACEWAYS AND BOXES
16140	WIRING DEVICES
16145	LIGHTING CONTROL DEVICES
16410	ENCLOSED SWITCHES AND CIRCUIT BREAKERS
16442	PANELBOARDS

Division 17 – Instrumentation (NIC)**Exhibits**

A-0.0	COVER SHEET
A-1.1	EXISTING FLOOR PLAN
A-1.2	PROPOSED FLOOR PLAN
A-1.3	DEMOLITION PLAN
A-1.4	ENTRY PLAN
A-1.5	PROPOSED ROOM FINISH PLAN
A-2.1	SECTIONS, CANOPY ROOF PLAN
A-2.2	SECTIONS, DETAIL WINDOW FLASHING, WEAPONS SIGN
A-2.3	SECTION & PLAN
A-3.1	FINISH SCHEDULE AND DOOR SCHEDULE
A-3.2	WINDOW SCHEDULE
M-1.0	EXISTING MECHANICAL FLOOR PLAN
M-1.1	PROPOSED FLOOR PLAN
E-0.1	LIGHTING FIXTURE SCHEDULE
E-1.0	EXISTING POWER PLAN
E-1.1	PROPOSED POWER PLAN
E-2.0	EXISTING LIGHTING PLAN & PROPOSED LIGHTING PLAN





PROPOSED FLOOR PLAN
SCALE: 1/4" = 1'-0"

- NOTES:**
1. Level 3 Ballistic material at Control Room and behind Reception Desk
 2. Ballistic material behind Gun Lockers
 3. Intercom/Panic Button at Control Room, Pat-down Rm, X-ray and Reception
 4. Monitors in Control Room and Reception Desk
 5. ADA door release at entrance doors, exit doors, and ADA gate.
 6. Five cameras w/ zoom mechanism
 7. Lock Out mechanism at exterior doors

DRAWING #
A-1.2
DATE: 6-11-12

Designed by: GCH
 Drawn by: GCH
 Reviewed by: NK
 Reviewed by: RD


BID SET - Revised Addendum #2

Fulton County Juvenile Court
 Entrance Security Renovation
 385 Pryor Street NW
 Atlanta, GA 30312

Rev.	Description	Date
1	Add Camera Location - Rm	4-2-12
2	Add Privacy Wall - ATV Room	4-5-12
	See Drawing Descriptions	

studio ALA
 3211 Peachtree Road
 Suite 500
 Atlanta, GA 30328
 404-477-2024
 studioala.net





PROPOSED POWER PLAN
SCALE: 1/4" = 1'-0"

- GENERAL NOTES:**
1. PROVIDE A RECORDED ELECTRICAL CONNECTION TO RECEIVING DOOR OPERATOR. DOOR SHALL BE RECORDED TO THE ELECTRICAL CONTROL PANEL. PROVIDE RECOMMENDATIONS OF UNIT WITH THE DOOR VENDOR PRIOR TO ORDERING. ALL PACKAGES AND CIRCUITING SHALL BE FOUNDED CONCERNED WITHIN THE DOOR FRAME OR DOOR VENDOR PRIOR TO ORDERING.
 2. PROVIDE A 20A, 250V ELECTRICAL CONNECTION FOR THE RECEIVING DOOR ANNUNCIATOR. PROVIDE RECOMMENDATIONS OF UNIT WITH THE DOOR VENDOR PRIOR TO ORDERING.
 3. PROVIDE ELECTRICAL CONNECTION AND INTERLOCK CONTROL'S FOR ACCESSIBLE DOOR OPERATOR. POWER CONNECTION SHALL BE MADE TO DOOR OPERATOR IN HEADER.
 4. RELOCATE THE EXISTING POWER AND COMMUNICATION CONNECTIONS FOR THE RELOCATED JURY UNIT. COORDINATE RELOCATION OF EQUIPMENT WITH OWNER AND VENDOR PRIOR TO START OF WORK.
 5. EXISTING FLOOR BOX SHALL BE REISED TO POWER OWNERS EQUIPMENT AS SHOWN. ADDITIONAL COORDINATING MAY BE REQUIRED AS SPECIFIED.
 6. EXISTING CIRCUIT (HARDWIRED) TO A SPARE CIRCUIT BREAKER WITHIN ELECTRICAL DISTRIBUTION PANEL AS SHOWN. IF NO SPARE CIRCUIT BREAKERS EXIST, THE CONTRACTOR SHALL PROVIDE A NEW BREAKER COMPATIBLE WITH THE PANEL MANUFACTURER. INTERLOCKING PLACING OF NEW BREAKERS SHALL EXCEED THE AVAILABLE FACTS (CONST) OF THE PANEL/BUILDING.
 7. PROVIDE BACKWAY STRIP-UPS WITHIN BASE OF TURNSTILE UNIT. PROVIDE A 4"X6" ANCHOR BOX VENDOR PRIOR TO ORDERING. FIELD CONTRACTOR SHALL PROVIDE A 1/2" BACKWAY FROM CAMERA LOCATION TO EXISTING COMMAND CENTER. INSTANT CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER. PROVIDE CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER AS REQUIRED FOR CCTV. COORDINATE EXISTING REQUIREMENTS WITH THE OWNER.
 8. PROVIDE A 1/2" BACKWAY FROM CAMERA TO EXISTING COMMAND CENTER. PROVIDE CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER AS REQUIRED FOR CCTV. COORDINATE EXISTING REQUIREMENTS WITH THE OWNER.
 9. PROVIDE A FUSED FLOOR POWER AND DATA/TELEPHONE OUTLET TO SERVE JURY UNIT. OUTLET BOXES SHALL BE STUBBED UP IN AN ACCESSIBLE AREA UNDER THE MILLWORK. COORDINATE EXACT PLACEMENT PRIOR TO DEMOLITION OF THE EXISTING FLOORING.
 10. PROVIDE AND ELECTRICAL AND NETWORKING CONNECTION TO THE NEW MEDIA DETECTOR UNIT. COORDINATE EXACT CONNECTION PLACEMENT WITH THE EQUIPMENT VENDOR OR VENDORS.
 11. PROVIDE ELECTRICAL CONNECTION TO MICHIGAN UNIT. FEEDER SHALL BE ROUNDED WITHIN EXISTING CONCEALED CONDUIT. PROVIDE A 1/2" BACKWAY FROM CAMERA TO EXISTING COMMAND CENTER. PROVIDE CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER AS REQUIRED FOR CCTV. COORDINATE EXISTING REQUIREMENTS WITH THE OWNER.
 12. PROVIDE A MOUNTING BRACKET CONNECTION AND ELECTRICAL GROUND FOR CONNECTION TO MONITOR. PROVIDE EXACT MOUNTING HEIGHT AND LOCATION WITH THE EXISTING ELECTRICAL POWER CIRCUIT AND ELECTRICAL GROUNDING. PROVIDE A 1/2" BACKWAY FROM CAMERA TO EXISTING COMMAND CENTER. PROVIDE CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER AS REQUIRED FOR CCTV. COORDINATE EXISTING REQUIREMENTS WITH THE OWNER.
 13. NEW PAINT-TIT-ROOM CAMERA TO MATCH EXISTING. EXISTING 1/2" BACKWAY FROM CAMERA LOCATION TO EXISTING COMMAND CENTER. PROVIDE CONTROL AND VIDEO CAMERA WITHIN CAMERA LOCATION TO EXISTING COMMAND CENTER AS REQUIRED FOR CCTV. COORDINATE EXISTING REQUIREMENTS WITH THE OWNER.
- GENERAL NOTES:**
1. CONTRACTOR SHALL VERIFY THE PROJECT SHALL CONSIST OF PROVIDING ALL LABOR, MATERIAL, EQUIPMENT, TOOLING AND OTHER ITEMS AS NECESSARY FOR A COMPLETE OPERATIONAL AIRWAY AREA ELECTRICAL SYSTEM.
 2. CONTRACTOR SHALL VISIT THE SITE PRIOR TO PROVIDING BIDS AND COMMENCEMENT OF WORK AND SHALL VERIFY ALL CONDITIONS SHALL BE AS SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONDITIONS WHICH ARE NOT AS SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONDITIONS WHICH ARE NOT AS SHOWN.
 3. ALL WORK SHALL BE INSTALLED IN A PROFESSIONAL MANNER AND THE ARCHITECT RESERVES THE RIGHT TO MAKE CORRECTIVE CHANGES AND REVISES ON DESIGN AND WORK WHICH IS DEEMED REFEROR TO ACCEPTABLE STANDARDS.
 4. ALL WORK SHALL CONFORM TO THE 2011 NATIONAL ELECTRICAL CODE WITH THE LATEST AMENDMENTS, GEORGIA ENERGY CODE AND NATIONAL FIRE ALARM CODE. CONTRACTOR SHALL VERIFY ALL PERMITS, FEES AND OTHER COSTS ASSOCIATED WITH LOCAL AUTHORITY HAVING JURISDICTION OVER THE WORK OF OTHER TRADES.
 5. CONTRACTOR SHALL VERIFY THE WORK AS FAST AS THE JOB SCHEDULE PERMITS SO AS TO NOT HINDER THE WORK OF OTHER TRADES.
 6. ELECTRICAL SUB-CONTRACTORS SHALL EXISTING ELECTRICAL CONNECTION AND PROTECTION REQUIREMENTS WITH THE OWNER. THE CONTRACTOR SHALL VERIFY ALL EXISTING ELECTRICAL CONNECTIONS TO CONFORM NEARLY ALL 2011 NATIONAL ELECTRICAL CODE AND FIELD ARCHITECT SHOULD VERIFY ALL EXISTING ELECTRICAL SUB-CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.
 7. ELECTRICAL SUB-CONTRACTOR SHALL VERIFY ALL EXISTING ELECTRICAL CONNECTIONS TO CONFORM NEARLY ALL 2011 NATIONAL ELECTRICAL CODE AND FIELD ARCHITECT SHOULD VERIFY ALL EXISTING ELECTRICAL SUB-CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES.

DRAWING # **E-1.1**

DATE: 10-18-11

Designed By: TLM
 Drawn By: TLM
 Checked By: JPM
 Approved By: JPM

PROPOSED ELECTRICAL PLAN

DATE: 10/18/11

Fulton County Juvenile Court Entrance Security Renovation

395 Pryor Street NW
 Atlanta, GA 30312

NO.	DESCRIPTION	DATE	BY
1	ELEC. ADDENDUM #1	4/25/11	TLM
2	COORDINATION REV.	4/29/11	TLM
3	DATE		

studio ALA

2221 Peachtree Road
 Suite 400
 Atlanta, GA 30309
 404-477-2526
 studioala.com

