



Fulton County, GA

Department of Purchasing & Contract Compliance

Felicia Strong-Whitaker, Interim Director

April 22, 2013

Re: 13ITB03281K-DJ, Fulton County Jail – Security Locks Retrofit

Dear Bidders:

Attached is one (1) copy of Addendum 3, hereby made a part of the above referenced Invitation To Bid (ITB), **#13ITB03281K-DJ, Fulton County Jail – Security Locks Retrofit.**

Except as provided herein, all terms and conditions in the ITB referenced above remain unchanged, in full force and effect.

Sincerely,

Donna Jenkins

Donna Jenkins
Chief Assistant Purchasing Agent

Winner 2000 - 2009 Achievement of Excellence in
Procurement Award • National Purchasing Institute



130 Peachtree Street, S.W., Suite 1168 • Atlanta, GA 30303 • (404) 612-5800

**13ITB03281K-DJ, Fulton County Jail – Security
Addendum No. 3**

ACKNOWLEDGEMENT OF ADDENDUM NO. 3

The undersigned Bidder acknowledges receipt of this addendum by returning one (1) copy of this form with the Bid package to the Fulton County Purchasing Department, Public Safety Building, 130 Peachtree Street, Suite 168, Atlanta, Georgia 30303 by the Bid due date and time **Monday, May 13, 2013, 11:00 A.M.**

This is to acknowledge receipt of Addendum No. 3, _____ day of _____, 2013.

_____ Legal Name of Bidder

_____ Signature of Authorized Representative

_____ Title

**13ITB03281K-DJ, Fulton County Jail – Security
Addendum No. 3**

This Addendum forms a part of the contract documents and **modifies** the original ITB documents as noted below:

Question 1. The drawings call for 4 release cabinets (note 5) per floor. However, release cabinets should not be required for swinging doors. Also, where release cabinets are required for sliding devices, there should be 1 release cabinets per cellblock. Please clarify or confirm.

Response: Release cabinets are not required for zones consisting of swinging cell doors. Yes, there should be one (1) release cabinet per sliding door zone.

Question 2. 2nd floor north tower, 3rd floor north tower, and 3rd floor south tower do not call for a new wedge or sliding device. Is this correct? It calls for note 4, but I'm not sure what all this consists of. Does note 4 require a new lock, and if so, can you specify what type?

Response: Note 4 pertains to heavy duty adjustable hinges to be installed per the County's discretion. All swing door cells on floors 2 and 3, in both the North and South towers, will require new locks and corresponding lock pockets.

Question 3. On the 7th floor north tower, 2 of the 6 cell blocks are drawn to have swinging doors, but the notes (notes 3 & 6) call for the doors to have sliders installed. If the drawings are correct and these doors are swinging doors, will they require new wedges? Please clarify.

Response: Zones 300 and 400 on 7 North are swing door cells and as such will require new locks and the lock pocket as specified. The remaining four (4) zones have sliding doors.

Question 4. On the 7th floor north tower mezzanine, 2 of the 6 cell blocks are drawn to have swinging doors, but the notes (notes 3 & 6) call for the doors to have sliders installed. If the drawings are correct and these doors are swinging doors, will they require new wedges? Please clarify.

Response: Zones 300 and 400 on 7 North are swing door cells and as such will require new locks and the lock pocket as specified. The remaining four (4) zones have sliding doors.

Question 5. On the 7th floor south tower, 2 of the 6 cell blocks are drawn to have swinging doors, but the note (note 3) calls for the doors to have sliders installed. If the drawings are correct and these doors are swinging doors, will they require new wedges? Please clarify.

Response: All doors on 7 south are sliding doors. This is a standardized note in the bid drawings.

Question 6. On the 7th floor south tower mezzanine, 2 of the 6 cell blocks are drawn to have swinging doors, but the note (note 3) calls for the doors to have sliders installed. If the drawings are correct and these doors are swinging doors, will they require new wedges? Please clarify.

Response: All doors on 7 south are sliding doors. This is a standardized note in the bid drawings.

Question 7. Addendum #2 calls for 2 keys per lock opening. This will equate to 36 keys for an 18 cell cellblock if all doors are keyed alike (around 1800 keys total). Please confirm that this is what is required.

Response: This is correct. Two (2) keys per lock opening.

**13ITB03281K-DJ, Fulton County Jail – Security
Addendum No. 3**

Question 8. Five SD88 Locking Devices have already been upgraded and meet the specifications. Are the individual releases for these doors to be reworked, holes plugged, and tied into the new manual release system or are these devices to be replaced?

Response: The existing devices are to be reworked and tied into the new manual release system.

Question 9. Nine swing door locks have already been upgraded with new locks and lock pockets and meet the specifications. Are these locks and lock pockets to remain or are they to receive a new lock and lock pocket?

Response: These nine (9) lock and pockets are to remain.

Question 10. Please clarify the following items:

- Cell doors in Dayroom N7-300 and N7-400 are shown as swing cell doors. These doors are noted “3”, which is sliding door hardware. What is correct?

Response: Zones 300 and 400 on 7 North consist of swing doors and should have new locks and lock pockets installed per the specifications.

- All doors in South 6th floor and 6th floor mezzanine are noted “1” & “3”. “1” is swing door hardware and “3” is sliding door hardware. Which is correct?

Response: All cell doors on both 6 South and 6 North are sliding doors and should be retrofitted as per the bid specifications for sliding cell doors.

- All doors in South 7th floor and 7th floor mezzanine are noted “1” & “3”. “1” is swing door hardware and “3” is sliding door hardware. Which is correct? Note: Cell doors in Dayrooms S7-400 and S7-500 are shown as swing doors and all others are shown as sliding cell doors.

Response: All doors on 7 South are sliding cell doors and should have new sliding operators installed as per the bid specifications.